




| Activity ID        | Activity Name               | BL1 Duration | Original Duration | Actual Duration | Start     | Finish    |
|--------------------|-----------------------------|--------------|-------------------|-----------------|-----------|-----------|
| <b>Phase 1</b>     |                             |              |                   |                 |           |           |
| <b>Projectwide</b> |                             | 124          | 124               | 0               | 27-Nov-12 | 22-May-13 |
| A1000              | Advanced Warning Signs      | 2            | 2                 | 0               | 27-Nov-12 | 28-Nov-12 |
| A0500              | Start Construction          | 0            | 0                 | 0               | 27-Nov-12 |           |
| A1010              | SWPPP                       | 1            | 1                 | 0               | 29-Nov-12 | 29-Nov-12 |
| A1060              | Traffic Control: Phase 1    | 1            | 1                 | 0               | 16-Jan-13 | 16-Jan-13 |
| A1210              | New Water Line              | 29           | 29                | 0               | 04-Feb-13 | 14-Mar-13 |
| A1220              | 6" Rip Rap                  | 7            | 7                 | 0               | 15-Mar-13 | 25-Mar-13 |
| A1270              | Permanent EB Sign & Pav Mar | 2            | 2                 | 0               | 16-May-13 | 17-May-13 |
| A1240              | Switch Traffic to New EB    | 3            | 3                 | 0               | 20-May-13 | 22-May-13 |
| <b>Bridge</b>      |                             | 116          | 116               | 0               | 30-Nov-12 | 15-May-13 |
| A1020              | EB Drill Shaft              | 11           | 11                | 0               | 30-Nov-12 | 14-Dec-12 |
| A1040              | EB Columns                  | 11           | 11                | 0               | 04-Dec-12 | 18-Dec-12 |
| A1030              | WB Drill Shaft              | 16           | 16                | 0               | 17-Dec-12 | 10-Jan-13 |



# CON511 – BASIC CONSTRUCTION SCHEDULE ANALYSIS

## Introduction

# Course Objectives


- The application of pertinent items from the 2014 TxDOT Standard Specifications for Construction and Maintenance of Highways, Streets, and Bridges (Specifications or Specs.).
- The availability and content of other internal resources (i.e., Construction Division and TxDOT manuals).
- The ability to review a contractor's schedule submission and evaluate its compliance with specification requirements.
- The ability to review a contractor's scheduling logic and understand how it coincides with contract time charges and project progress.
- The ability to review contractor schedule updates and compare progress with monthly estimates.

## Upon completion...


- Review a contractor's preconstruction schedule for compliance with specification requirements and constructability.
- Monitor project progress and constructability compared with monthly estimates.
- Initially identify time impacts to the project using critical thinking skills.
- Engage the contractor regarding time and schedule concerns.
- Apply best practices and create your own best practices for schedule analysis.


***Note: Every construction project is unique and creates its own personality depending upon the scope of work, existing conditions, unforeseen issues, and contractor interaction. Participants should develop critical thinking skills that help address a broad spectrum of issues likely to be faced on a variety of construction projects.***

# Time for TxDOT Construction Projects




# Cost for TxDOT Construction Projects





| Activity ID        | Activity Name               | BL1 Duration | Original Duration | Actual Duration | Start     | Finish    |
|--------------------|-----------------------------|--------------|-------------------|-----------------|-----------|-----------|
| <b>Phase 1</b>     |                             |              |                   |                 |           |           |
| <b>Projectwide</b> |                             | 124          | 124               | 0               | 27-Nov-12 | 22-May-13 |
| A1000              | Advanced Warning Signs      | 2            | 2                 | 0               | 27-Nov-12 | 28-Nov-12 |
| A0500              | Start Construction          | 0            | 0                 | 0               | 27-Nov-12 |           |
| A1010              | SWPPP                       | 1            | 1                 | 0               | 29-Nov-12 | 29-Nov-12 |
| A1060              | Traffic Control: Phase 1    | 1            | 1                 | 0               | 16-Jan-13 | 16-Jan-13 |
| A1210              | New Water Line              | 29           | 29                | 0               | 04-Feb-13 | 14-Mar-13 |
| A1220              | 6" Rip Rap                  | 7            | 7                 | 0               | 15-Mar-13 | 25-Mar-13 |
| A1270              | Permanent EB Sign & Pav Mar | 2            | 2                 | 0               | 16-May-13 | 17-May-13 |
| A1240              | Switch Traffic to New EB    | 3            | 3                 | 0               | 20-May-13 | 22-May-13 |
| <b>Bridge</b>      |                             | 116          | 116               | 0               | 30-Nov-12 | 15-May-13 |
| A1020              | EB Drill Shaft              | 11           | 11                | 0               | 30-Nov-12 | 14-Dec-12 |
| A1040              | EB Columns                  | 11           | 11                | 0               | 04-Dec-12 | 18-Dec-12 |
| A1030              | WB Drill Shaft              | 16           | 16                | 0               | 17-Dec-12 | 10-Jan-13 |



# CON511 – BASIC CONSTRUCTION SCHEDULE ANALYSIS

## Module 1: Background Information – Part 1

## Module 1 Objectives

- Understand what items and articles in the 2014 Specifications have scheduling related elements
- Identify other resources containing construction scheduling and monitoring information
- Understand how time charges accrue on construction projects
- Understand how weather impacts construction activities and time charges

*It is important to understand the specifications, the requirements of the contractor, and scheduling practices and principles for all types of projects. Scheduling and scheduling analysis is NOT just for the mega projects that cost hundreds of millions of dollars.*

# Schedule Specification Requirements for the Preconstruction Phase

**Article 8.1** in TxDOT's Standard Specification states, "Begin work within 30 calendar days after the authorization date to begin work".

- An example: If the work authorization is dated March 1<sup>st</sup>, the first day *after* is March 2<sup>nd</sup> and starts the 30-calendar day count. Work and time charges should begin by March 30<sup>th</sup>. Work can begin before this if the preconstruction conference has been held.

**Article 4.2 – Preconstruction Conference:** Before starting work, schedule and attend a preconstruction conference with the engineer.

- “failure to schedule and attend a preconstruction conference is **not** grounds for delaying the beginning of working day charges.”

## Schedule Specification Requirements for the Preconstruction Phase

**Article 8.5.2** states, “**Before** starting work, prepare and submit a progress schedule based on the sequence of work and traffic control plan shown in the contract. Prepare the progress schedule as a bar chart or critical path method (CPM) as shown on the plans.”

**Article 8.5.5.1** states, “Seven calendar days **before** the preconstruction meeting, prepare and submit a hard copy of the schedule using the bar chart method.”

Chapter 3 of Section 4 includes details about the preconstruction conference that relate to a contractor's schedule:

- Number of work days
- Start date
- Completion date
- Holidays, tax holidays, or other days the highway may not be closed
- Major phases on the contract
- Detailed progress schedule outlining the manner of prosecution of work intended to complete work in the allotted time
- Work plans
- Criteria on working day charges and temporary suspension of work (notify the area engineer [AE] at least 24 hours before beginning work in any new operation)
- Explain the traffic control plan (TCP) and its sequence during the contract
- Determine the contractor's plans for implementing the TCP

## The plan should include:

- Estimated start date.
- Estimated completion date.
- Project schedule—contractor's project schedule to be furnished to AE.
- Acceptable schedule required before work can begin.
- Schedule updates required each month.
- Contractor cannot revise the schedule without notifying TxDOT in writing.
- Contractor responsible for initiating time impact analysis process for delays.

# Schedule Specification Requirements for the Construction Phase

**Article 8.5** states:

“Prepare, maintain, and **submit** project schedules. Project schedules are used to convey the Contractor’s intended work plan to the Department. Prepare project schedules with a level of effort sufficient for the work being performed.”

A designated person is required by the specifications to develop and maintain the progress schedule (**Article 8.5.1**).

**Article 8.5.5.1.1** states to “Update the project schedule and submit a hard copy when changes to the schedule occur or when requested.”

## Schedule Specification Requirements for the Construction Phase

**Article 8.3.4** requires that TxDOT provide the contractor with a time statement for the project. TxDOT accomplishes this on a monthly basis through the Contractor's monthly estimate package.

**Article 8.3.4** further states:

The contractor must protest time charges in writing and within 30 calendar days after receiving the time statement. Failure to protest within 30 calendar days indicates acceptance and no future consideration of that period will be permitted.

*Communication and documentation are key; while the Specifications are clear that the contractor must notify TxDOT in writing, it benefits TxDOT to engage with the contractor and notify them in writing as well.*

## Schedule Specification Requirements for the Construction Phase

**Article 8.5.2** says, “Include all planned work activities and sequences and show contract completion within the number of working days specified. Incorporate major material procurements, known utility relocations, and other activities that may affect the completion of the Contract in the progress schedule. **Show a beginning date, ending date, and duration in whole working days for each activity. Do not use activities exceeding 20 working days, unless agreed upon with the engineer. Show an estimated production rate per working day for each work activity, unless agreed upon with the engineer.**”

*Avoid confusing these default requirements for all schedules with CPM specific requirements conveyed in [Article 8.5.5.2](#)*

# Critical Path Method Specification Requirements

The default scheduling requirement in the specifications is ambiguous. If CPM is required, it is typically noted in the General Notes.

[Article 8.5.5.2](#) - Critical Path Method – Prepare and submit the schedule using CPM.

[Article 8.5.5.2.1](#) - Preliminary Schedule – Seven calendar days before the preconstruction meeting, submit both the plotted and electronic copies of the project schedule showing activities beginning with the authorization date to begin work and including activities to be performed within the first 90 calendar days from the work start date.

All elements of [Article 8.5.5.2.X.X](#) pertain to CPM scheduling

## Understanding Time and Time Charges

A **workweek** is defined as the method for charging working days to a project.

A **working day** is defined as “any day (other than Sunday or legal holiday) on which legal business can be conducted. Whether Saturday is a working day or not depends on the custom or usage of the trade or jurisdiction.”  
(<http://www.businessdictionary.com/definition/working-day.html>)

**Article 8.3** in TxDOT's Standard Specifications defines a workweek in one of five ways:

## 8.3.1.1. Five-Day Workweek

Working days will be charged Monday through Friday, excluding national holidays, regardless of weather conditions or material availability. The Contractor has the option of working on Saturdays. Provide sufficient advance notice to the Engineer when scheduling work on Saturdays. Work on Sundays and national holidays will not be permitted without written permission of the Engineer. If work requiring an Inspector to be present is performed on a Saturday, Sunday, or national holiday, and weather and other conditions permit the performance of work for 7 hr. between 7:00 A.M. and 6:00 P.M., a working day will be charged.

[Article 8.3](#) in TxDOT's Standard Specifications defines a workweek in one of five ways:

## [8.3.1.2. Six-Day Workweek](#)

Working days will be charged Monday through Saturday, excluding national holidays, regardless of weather conditions or material availability. Work on Sundays and national holidays will not be permitted without written permission of the Engineer. If work requiring an Inspector to be present is performed on a Sunday or a national holiday, and weather or other conditions permit the performance of work for 7 hr. between 7:00 A.M. and 6:00 P.M., a working day will be charged.

[Article 8.3](#) in TxDOT's Standard Specifications defines a workweek in one of five ways:

## [8.3.1.3. Seven-Day Workweek](#)

Working days will be charged Monday through Sunday, excluding national holidays, regardless of weather conditions or material availability. Work on national holidays will not be permitted without written permission of the Engineer. If work is performed on any of these holidays requiring an Inspector to be present, and weather or other conditions permit the performance of work for 7 hr. between 7:00 A.M. and 6:00 P.M., a working day will be charged.

[Article 8.3](#) in TxDOT's Standard Specifications defines a workweek in one of five ways:

## [8.3.1.4. Standard Workweek](#)

Working days will be charged Monday through Friday, excluding national or state holidays, if weather or other conditions permit the performance of the principal unit of work underway, as determined by the Engineer, for a continuous period of at least 7 hr. between 7:00 A.M. and 6:00 P.M., unless otherwise shown in the Contract. The Contractor has the option of working on Saturdays or state holidays. Provide sufficient advance notice to the Engineer when scheduling work on Saturdays. Work on Sundays and national holidays will not be permitted without written permission of the Engineer. If work requiring an Inspector to be present is performed on a Saturday, Sunday, or holiday, and weather or other conditions permit the performance of work for 7 hr. between 7:00 A.M. and 6:00 P.M., a working day will be charged.

[Article 8.3](#) in TxDOT's Standard Specifications defines a workweek in one of five ways:

## [8.3.1.5 Calendar Day](#)

Working days will be charged Sunday through Saturday, including all holidays, regardless of weather conditions, material availability, or other conditions not under the control of the Contractor.

Note:

[Article 8.3.1.6](#) allows TxDOT to charge working days as specified in the plans.

When the project plans or proposal do not specify how time charges are to accrue, the default in the Standard Specifications prevails. [Article 8.3.1](#) sets the default as a Standard Workweek.

### [8.3.1. Working Day Charges](#)


Working days will be charged in accordance with [Article 8.3.1.4](#), “Standard Workweek,” unless otherwise shown on the plans.



| Activity ID        | Activity Name               | BL1 Duration | Original Duration | Actual Duration | Start     | Finish    |
|--------------------|-----------------------------|--------------|-------------------|-----------------|-----------|-----------|
| <b>Phase 1</b>     |                             |              |                   |                 |           |           |
| <b>Projectwide</b> |                             | 124          | 124               | 0               | 27-Nov-12 | 22-May-13 |
| A1000              | Advanced Warning Signs      | 2            | 2                 | 0               | 27-Nov-12 | 28-Nov-12 |
| A0500              | Start Construction          | 0            | 0                 | 0               | 27-Nov-12 |           |
| A1010              | SWPPP                       | 1            | 1                 | 0               | 29-Nov-12 | 29-Nov-12 |
| A1060              | Traffic Control: Phase 1    | 1            | 1                 | 0               | 16-Jan-13 | 16-Jan-13 |
| A1210              | New Water Line              | 29           | 29                | 0               | 04-Feb-13 | 14-Mar-13 |
| A1220              | 6" Rip Rap                  | 7            | 7                 | 0               | 15-Mar-13 | 25-Mar-13 |
| A1270              | Permanent EB Sign & Pav Mar | 2            | 2                 | 0               | 16-May-13 | 17-May-13 |
| A1240              | Switch Traffic to New EB    | 3            | 3                 | 0               | 20-May-13 | 22-May-13 |
| <b>Bridge</b>      |                             | 116          | 116               | 0               | 30-Nov-12 | 15-May-13 |
| A1020              | EB Drill Shaft              | 11           | 11                | 0               | 30-Nov-12 | 14-Dec-12 |
| A1040              | EB Columns                  | 11           | 11                | 0               | 04-Dec-12 | 18-Dec-12 |
| A1030              | WB Drill Shaft              | 16           | 16                | 0               | 17-Dec-12 | 10-Jan-13 |

# CON511 – BASIC CONSTRUCTION SCHEDULE ANALYSIS

## Module 1: Background Information – Part 2



## Module 1 Objectives

- Understand what items and articles in the 2014 Specifications have scheduling related elements
- Identify other resources containing construction scheduling and monitoring information
- Understand how time charges accrue on construction projects
- Understand how weather impacts construction activities and time charges

*It is important to understand the specifications, the requirements of the contractor, and scheduling practices and principles for all types of projects. Scheduling and scheduling analysis is NOT just for the mega projects that cost hundreds of millions of dollars.*

**Article 8.3** in TxDOT's Standard Specifications defines a workweek in one of five ways:

## 8.3.1.1. Five-Day Workweek

Working days will be charged Monday through Friday, excluding national holidays, regardless of weather conditions or material availability. The Contractor has the option of working on Saturdays. Provide sufficient advance notice to the Engineer when scheduling work on Saturdays. Work on Sundays and national holidays will not be permitted without written permission of the Engineer. If work requiring an Inspector to be present is performed on a Saturday, Sunday, or national holiday, and weather and other conditions permit the performance of work for 7 hr. between 7:00 A.M. and 6:00 P.M., a working day will be charged.

[Article 8.3](#) in TxDOT's Standard Specifications defines a workweek in one of five ways:

## [8.3.1.2. Six-Day Workweek](#)

Working days will be charged Monday through Saturday, excluding national holidays, regardless of weather conditions or material availability. Work on Sundays and national holidays will not be permitted without written permission of the Engineer. If work requiring an Inspector to be present is performed on a Sunday or a national holiday, and weather or other conditions permit the performance of work for 7 hr. between 7:00 A.M. and 6:00 P.M., a working day will be charged.

[Article 8.3](#) in TxDOT's Standard Specifications defines a workweek in one of five ways:

## [8.3.1.3. Seven-Day Workweek](#)

Working days will be charged Monday through Sunday, excluding national holidays, regardless of weather conditions or material availability. Work on national holidays will not be permitted without written permission of the Engineer. If work is performed on any of these holidays requiring an Inspector to be present, and weather or other conditions permit the performance of work for 7 hr. between 7:00 A.M. and 6:00 P.M., a working day will be charged.

[Article 8.3](#) in TxDOT's Standard Specifications defines a workweek in one of five ways:

## [8.3.1.4. Standard Workweek](#)

Working days will be charged Monday through Friday, excluding national or state holidays, if weather or other conditions permit the performance of the principal unit of work underway, as determined by the Engineer, for a continuous period of at least 7 hr. between 7:00 A.M. and 6:00 P.M., unless otherwise shown in the Contract. The Contractor has the option of working on Saturdays or state holidays. Provide sufficient advance notice to the Engineer when scheduling work on Saturdays. Work on Sundays and national holidays will not be permitted without written permission of the Engineer. If work requiring an Inspector to be present is performed on a Saturday, Sunday, or holiday, and weather or other conditions permit the performance of work for 7 hr. between 7:00 A.M. and 6:00 P.M., a working day will be charged.

[Article 8.3](#) in TxDOT's Standard Specifications defines a workweek in one of five ways:

## [8.3.1.5 Calendar Day](#)

Working days will be charged Sunday through Saturday, including all holidays, regardless of weather conditions, material availability, or other conditions not under the control of the Contractor.

Note:

[Article 8.3.1.6](#) allows TxDOT to charge working days as specified in the plans.

When the project plans or proposal do not specify how time charges are to accrue, the default in the Standard Specifications prevails. [Article 8.3.1](#) sets the default as a Standard Workweek.


### [8.3.1. Working Day Charges](#)

Working days will be charged in accordance with [Article 8.3.1.4](#), “Standard Workweek,” unless otherwise shown on the plans.

# What impacts how many days a contractor works?



Regardless of how time charges are established in the contract, there are practical impacts to time that should be understood. When evaluating schedules for realistic durations, one must understand these impacts and adjust expectations based on reasonably expected impacts.



## Example of time impacts

A \$13.7 million project in the Tyler District to construct a Super 2 with a level-up and PFC surface over the entire roadway. The total project length is 10.788 miles. Additional information is below:

- 206 Working Days
- Standard Workweek
- 15 months of barricades

206 working days over 15 months results in an average of 13.7 chargeable days (i.e., working days) per month.

## Example of time impacts, continued

How many days within a year should we expect the contractor to work?

Account for Saturdays and Sundays:

| <b>Calendar Days<br/>Per Year</b> | <b>Weekend Days<br/>Per Year</b> | <b>Total Working Days Per<br/>Year</b> |
|-----------------------------------|----------------------------------|--|
| <b>365</b>                        | <b>104</b>                       | <b>261</b>                             |

## Example of time impacts, continued

How many days within a year should we expect the contractor to work?

Account for rain:

The National Oceanic and Atmospheric Administration (NOAA) is a good resource for understanding potential weather impacts to days available for the contractor to work. A good benchmark for rain is days with more than 0.1 in. of rain. Rainfall heavier than this often leads to the suspension of work.

| Year | Jan       | Feb        | Mar        | Apr        | May        | Jun       | Jul       | Aug       | Sep       | Oct        | Nov        | Dec       | Annual     |
|------|-----------|------------|------------|------------|------------|-----------|-----------|-----------|-----------|------------|------------|-----------|------------|
| 2014 | 2         | 6          | 5          | 2          | 8          | 9         | 7         | 1         | 3         | 7          | 5          | 8         | 63         |
| 2015 | 6         | 5          | 11         | 11         | 16         | 8         | 0         | 4         | 1         | 5          | 13         | 6         | 86         |
| 2016 | 2         | 4          | 5          | 8          | 6          | 4         | 4         | 9         | 2         | 2          | 3          | 8         | 57         |
| 2017 | 5         | 3          | 6          | 5          | 8          | 6         | 6         | 9         | 0         | 3          | 2          | 6         | 59         |
| 2018 | 5         | 12         | 4          | 6          | 1          | 2         | 5         | 4         | 9         | 11         | 5          | 9         | 73         |
| Mean | 4         | 6          | 6          | 6          | 8          | 6         | 4         | 5         | 3         | 6          | 6          | 7         | 68         |
| Max  | 6<br>2015 | 12<br>2018 | 11<br>2015 | 11<br>2015 | 16<br>2015 | 9<br>2014 | 7<br>2014 | 9<br>2017 | 9<br>2018 | 11<br>2018 | 13<br>2015 | 9<br>2018 | 86<br>2015 |
| Min  | 2<br>2016 | 3<br>2017  | 4<br>2018  | 2<br>2014  | 1<br>2018  | 2<br>2018 | 0<br>2015 | 1<br>2014 | 0<br>2017 | 2<br>2016  | 2<br>2017  | 6<br>2017 | 57<br>2016 |

## Example of time impacts, continued

How many days within a year should we expect the contractor to work?

Account for rain:

Not all rain occurs on a weekday. If we assume the rain days are just as likely to fall on any given day:

$68/365 = 18.6\%$  of calendar days receive 0.1-in. of rain or more

$18.6\% * 261 \text{ weekdays} = 48.6 \text{ weekdays}$  receive 0.1-in. of rain or more. Round to 48.

$261 - 48 = 213 \text{ working days}$

## Example of time impacts, continued

How many days within a year should we expect the contractor to work?

Account for holidays:

| No. | Holiday                     | Agency Status | Date       | Day of Week |
|-----|-----------------------------|---------------|------------|-------------|
| ①   | New Year's Day              | All Agencies  | 1/1/2019   | Tuesday     |
| 2   | Martin Luther King, Jr. Day | All Agencies  | 1/21/2019  | Monday      |
| 3   | President's Day             | All Agencies  | 2/18/2019  | Monday      |
| ④   | Memorial Day                | All Agencies  | 5/27/2019  | Monday      |
| ⑤   | Independence Day            | All Agencies  | 7/4/2019   | Thursday    |
| ⑥   | Labor Day                   | All Agencies  | 9/2/2019   | Monday      |
| ⑦   | Thanksgiving Day            | All Agencies  | 11/28/2019 | Thursday    |
| ⑧   | Day After Thanksgiving Day  | All Agencies  | 11/29/2019 | Friday      |
| ⑨   | Christmas Eve Day           | All Agencies  | 12/24/2019 | Tuesday     |
| ⑩   | Christmas Day               | All Agencies  | 12/25/2019 | Wednesday   |
| ⑪   | Day After Christmas Day     | All Agencies  | 12/26/2019 | Thursday    |

213 - 9 = 204 working days  
when accounting for  
weekends, rain, and  
holidays.

## Example of time impacts, continued

Some factors that could influence a contractor's ability to perform work are detailed in the specifications:

- Surface temperature for HMA paving:
  - [Article 341.4.7.1](#)
  - [Article 346.4.7.1](#)
- Temperature restrictions for concrete pavements
  - [Article 360.4.73.3](#)
- Surface conditions for reflectorized pavement markings
  - [Article 666.4.3.1](#)

| Air Temperature | Predicted Max Surface Temp. | Predicted Min. Surface Temp. |
|-----------------|-----------------------------|------------------------------|
| 35              | 36                          | 36                           |
| 40              | 42                          | 41                           |
| 50              | 55                          | 53                           |
| 60              | 68                          | 64                           |
| 70              | 80                          | 75                           |
| 80              | 93                          | 86                           |
| 90              | 106                         | 97                           |
| 100             | 118                         | 108                          |

## Example of time impacts, continued

Also, 0.1-in. of rain might not always prevent a contractor from performing work or resuming operations. Therefore, on some days, the contractor might not be charged a day, yet work is performed for less than seven continuous hours.

Even though there could be other reasons that work is not performed, this gives us a pretty good idea of the number of days we should expect the contractor to work.


- $204 \text{ working days} / 12 \text{ months per year} = 17 \text{ working days per month}$

**15 to 17 working days per month** is a good average value to assume for the number of days the contractor will perform work during a month.

A good rule of thumb is to assume that **180 to 205** real working days exist during a calendar year.

# Time Charges Summary


|  |                   |       |      |      |      |      |      |       |       |     |      |      |      |       |      |      |       |
|--|-------------------|-------|------|------|------|------|------|-------|-------|-----|------|------|------|-------|------|------|-------|
| Anticipated Real Days Required to Complete the Project |                   | 206   |      |      |      |      |      |       |       |     |      |      |      |       |      |      |       |
| Months of Barricades                                   |                   | 15    |      |      |      |      |      |       |       |     |      |      |      |       |      |      |       |
|  |                   | Sept. | Oct. | Nov. | Dec. | Jan. | Feb. | March | April | May | June | July | Aug. | Sept. | Oct. | Nov. | Total |
|  | Real Working Days | 17    | 17   | 14   | 12   | 14   | 11   | 15    | 16    | 14  | 17   | 17   | 17   | 17    | 17   | 14   | 229   |
| 8.3.1.1  | 5-Day Workweek    | 21    | 21   | 20   | 20   | 21   | 19   | 23    | 23    | 20  | 22   | 20   | 21   | 21    | 21   | 20   | 313   |
| 8.3.1.2  | 6-Day Workweek    | 25    | 26   | 24   | 24   | 25   | 23   | 27    | 27    | 25  | 26   | 25   | 26   | 25    | 26   | 24   | 378   |
| 8.3.1.3  | 7-Day Workweek    | 29    | 31   | 28   | 28   | 29   | 27   | 30    | 30    | 30  | 30   | 30   | 31   | 29    | 31   | 28   | 441   |
| 8.3.1.4  | Standard Workweek | 17    | 17   | 14   | 12   | 14   | 11   | 15    | 16    | 14  | 17   | 17   | 17   | 17    | 17   | 14   | 229   |
| 8.3.1.5  | Calendar Day      | 30    | 31   | 30   | 31   | 31   | 28   | 30    | 30    | 31  | 30   | 31   | 31   | 30    | 31   | 30   | 455   |



| Activity ID        | Activity Name               | BL1 Duration | Original Duration | Actual Duration | Start     | Finish    |
|--------------------|-----------------------------|--------------|-------------------|-----------------|-----------|-----------|
| <b>Phase 1</b>     |                             |              |                   |                 |           |           |
| <b>Projectwide</b> |                             | 124          | 124               | 0               | 27-Nov-12 | 22-May-13 |
| A1000              | Advanced Warning Signs      | 2            | 2                 | 0               | 27-Nov-12 | 28-Nov-12 |
| A0500              | Start Construction          | 0            | 0                 | 0               | 27-Nov-12 |           |
| A1010              | SWPPP                       | 1            | 1                 | 0               | 29-Nov-12 | 29-Nov-12 |
| A1060              | Traffic Control: Phase 1    | 1            | 1                 | 0               | 16-Jan-13 | 16-Jan-13 |
| A1210              | New Water Line              | 29           | 29                | 0               | 04-Feb-13 | 14-Mar-13 |
| A1220              | 6" Rip Rap                  | 7            | 7                 | 0               | 15-Mar-13 | 25-Mar-13 |
| A1270              | Permanent EB Sign & Pav Mar | 2            | 2                 | 0               | 16-May-13 | 17-May-13 |
| A1240              | Switch Traffic to New EB    | 3            | 3                 | 0               | 20-May-13 | 22-May-13 |
| <b>Bridge</b>      |                             | 116          | 116               | 0               | 30-Nov-12 | 15-May-13 |
| A1020              | EB Drill Shaft              | 11           | 11                | 0               | 30-Nov-12 | 14-Dec-12 |
| A1040              | EB Columns                  | 11           | 11                | 0               | 04-Dec-12 | 18-Dec-12 |
| A1030              | WB Drill Shaft              | 16           | 16                | 0               | 17-Dec-12 | 10-Jan-13 |

# CON511 – BASIC CONSTRUCTION SCHEDULE ANALYSIS

## Module 2: Assessment of Construction Schedules



## Module 2 Objectives

- Understand the difference between work activity as a component of the contractor's schedule and a pay item as a component of the TxDOT monthly estimate.
- Sort TxDOT pay items and use the sorted list to map the contractor's schedule activities to ensure necessary items are scheduled.
- Evaluate the feasibility of the contractor's production rate(s) and activity duration(s).
- Understand the types of logical schedule activity relationships and assess the reasonableness of the relationships.
- Identify the critical path within a schedule and to track any change(s) to the critical path.
- Evaluate a contractor's schedule update and compare it to TxDOT monthly estimates for accuracy and reasonableness.
- Develop a framework to engage the contractor regarding schedule concerns.



# 1. SCHEDULE REQUIREMENTS

## Required Components in Schedule

- The contractor provides TxDOT with a schedule that illustrates how the contractor intends to construct the project.
  - This schedule should include activities and logic that fit together to achieve an end product...we could call this the Work Breakdown Structures (WBS)
- **Article 8.5.2** lists the elements required in the Schedule:
  - **Contract completion within the number of working days**
  - **Begin date** for each activity
  - **End date** for each activity
  - **Activity duration**
  - **Production rate** for each activity



## **2. MAPPING ITEMS TO ACTIVITIES**


---

# Work Breakdown Structure (WBS)

- The WBS captures “chunks” of work used to construct the project
- For highway projects, the WBS typically includes:
  - Phasing or Milestones
  - Work type
    - i.e., roadway work, bridge work, drainage work
  - Seasonal work
- Look for logical structures based on the scope of the project

# Work Breakdown Structure (WBS) in Schedule Using Type of Work

- Work activities in schedule should be well presented by the work breakdown structure (WBS).



- **Planned construction** (e.g., place storm drain, pour columns, lay HMA).
- **Major material procurements** (e.g., bridge beams, precast inlets or boxes, seal coat rock).
- **Known utility relocations** (e.g., aerial lines such as electrical or communication, subsurface lines such as water or communication).

# Work Breakdown Structure (WBS) in Schedule Using Phasing

- Work activities in schedule should be well presented by the work breakdown structure (WBS).

| Baylor County US 82 - 0156-06-052 |                    |             |           |
|-----------------------------------|--------------------|-------------|-----------|
| 1000                              | Project Duration   | 09-Jul-18 A | 24-May-19 |
| 1020                              | Set Barricades     | 09-Jul-18 A | 12-Jul-18 |
| 1030                              | SW3P               | 12-Jul-18 A | 17-Jul-18 |
| 1040                              | Install Culvert #1 | 12-Jul-18 A | 15-Aug-18 |
| 1050                              | Install Culvert #2 | 16-Aug-18   | 23-Aug-18 |
| 1060                              | Install Culvert #3 | 24-Aug-18   | 04-Oct-18 |

- Project wide elements
- Large culvert construction
  - It might be better if the culvert construction was its own WBS with more detail.

| Phase 1 |                         |           |           |
|---------|-------------------------|-----------|-----------|
| 1080    | Temporary Pavement      | 16-Aug-18 | 24-Aug-18 |
| 1090    | Shift Traffic           | 27-Aug-18 | 27-Aug-18 |
| 1100    | Install PCTB            | 28-Aug-18 | 04-Sep-18 |
| 1110    | Remove ASB              | 05-Sep-18 | 13-Sep-18 |
| 1120    | Remove Concrete Pav     | 14-Sep-18 | 26-Sep-18 |
| 1130    | Excavation/Embankme     | 27-Sep-18 | 06-Nov-18 |
| 1140    | Cement Treat Subgrac    | 06-Nov-18 | 13-Nov-18 |
| 1150    | 12" Flex Base           | 12-Nov-18 | 27-Nov-18 |
| 1160    | MC-30 Prime Coat        | 03-Dec-18 | 03-Dec-18 |
| 1170    | One Course Seal         | 07-Dec-18 | 07-Dec-18 |
| 1180    | 2" HMA Type D           | 10-Dec-18 | 11-Dec-18 |
| 1190    | Backfill & Dress Slopes | 13-Dec-18 | 14-Dec-18 |

- Roadway rehabilitation
  - It might be better if the detour work was its own WBS with more detail.

| Phase 2 |                      |           |           |
|---------|----------------------|-----------|-----------|
| 2210    | Temporary Pavement   | 17-Dec-18 | 27-Dec-18 |
| 2220    | Move PCTB            | 28-Dec-18 | 04-Jan-19 |
| 2230    | Shift Traffic        | 07-Jan-19 | 07-Jan-19 |
| 2240    | Excavation/Embankme  | 29-Jan-19 | 01-Mar-19 |
| 2250    | Cement Treat Subgrac | 04-Mar-19 | 11-Mar-19 |

- Roadway rehabilitation
  - It might be better if the detour work was its own WBS with more detail.

- The scope of work is similar across multiple phases (e.g., Phase 1 and Phase 2 include roadway reconstruction)
- Includes logical breaks to distinguish between phases

# Pay Item to Schedule Activity

- Contractors can create activities in the schedule by:
  - Considering each pay item as a schedule activity
  - Combining multiple pay items into a single schedule activity
    - E.g., Construct storm drain network A
      - This could include inlets, junction boxes, and various pipe sizes
    - E.g., Construct traffic signal
      - This includes all signal related components
  - Separate a pay item into multiple schedule activities
    - E.g., Construct bridge deck might have an item for set panels, tie steel, set forms, pour deck, groove deck.
      - Most of these items are paid under a single item

# Discrepancy Between Pay Items and Work Activities

- Pay items in estimates and work activities in schedules are usually different.

Longer than schedules

| ITEM CODE | DESCRIPTION                            | UNIT | UNIT PRICE | BID QUANTITY | TOTAL PRICE |
|-----------|--|------|------------|--------------|-------------|
| 05022001  | BARRICADES, SIGNS AND TRAFFIC HANDLING | MO   | \$ 2,000   | 12.000       | \$ 24,000   |
| 59692006  | WATER MAIN PIPE (PVC)(12IN)            | LF   | \$ 40      | 1,360.000    | \$ 54,400   |
| 59692011  | WATER MAIN PIPE (STL)(12IN)            | LF   | \$ 120     | 410.000      | \$ 49,200   |
| 59692075  | WET CONNECTION (12IN)                  | EA   | \$ 1,000   | 6.000        | \$ 6,000    |
| 59692095  | GATE VALVE (12IN)                      | EA   | \$ 3,000   | 4.000        | \$ 12,000   |
| 04162001  | DRILL SHAFT (18 IN)                    | LF   | \$ 100     | 94.000       | \$ 9,400    |
| 04162002  | DRILL SHAFT (24 IN)                    | LF   | \$ 90      | 228.000      | \$ 20,520   |
| 04162003  | DRILL SHAFT (30 IN)                    | LF   | \$ 150     | 858.000      | \$ 128,700  |
| 04302002  | CL C CONC FOR EXT STR (ABUT)           | CY   | \$ 1,500   | 27.000       | \$ 40,500   |
| 04302003  | CL C CONC FOR EXT STR (BENT)           | CY   | \$ 1,200   | 89.700       | \$ 107,640  |

Example of Pay Items in Estimates

| Projectwide |                          | Bridge |                         |
|-------------|--------------------------|--------|-------------------------|
| A1000       | Advanced Warning Signs   | A1020  | EB Drill Shaft          |
| A0500       | Start Construction       | A1040  | EB Columns              |
| A1010       | SWPPP                    | A1090  | Abutment 1 & 2: Phase 1 |
| A1060       | Traffic Control: Phase 1 | A1100  | Bent Caps: 2 - 10       |
| A1210       | New Water Line           | A1180  | Pan Girder              |

Example of Work Activities in Schedules

# Where to start?

- Sometimes the project and schedule feels too big to find a place to start.
  - Understanding your high-cost items helps.
  - Sort the estimate or estimate & quantity sheet from highest total cost to lowest total cost.
  - This will allow you to see your high-cost items.
    - It will also allow you to identify these items in the contractor's schedule to ensure those items are included.

# Sorting & Mapping Process: a multi-step process

- Sort and Map pay items in monthly estimate to work activities in schedule
  - Sort your estimate first to make sure the most expensive items are in the schedule

a. Sort the pay items based on total price in the descending order

It doesn't take that many items to consume 80% of the total project cost.

| Table of Project Estimate |   |      |                |              |                |                 |                |
|---------------------------|---|------|----------------|--------------|----------------|-----------------|----------------|
| ITEM CODE                 | DESCRIPTION                             | UNIT | UNIT PRICE     | BID QUANTITY | TOTAL PRICE    | CUMULATIVE COST | CUMULATIVE (%) |
| 03446034                  | SUPERPAVE MIXTURES SP-C PG64-22         | TON  | \$97.00        | 23,670.000   | \$2,295,990.00 | \$2,295,990.00  | 13.7%          |
| 04236001                  | RETAINING WALL (MSE)                    | SF   | \$60.00        | 29,949.000   | \$1,796,940.00 | \$4,092,930.00  | 24.4%          |
| 05006001                  | MOBILIZATION                            | LS   | \$1,400,000.00 | 1.000        | \$1,400,000.00 | \$5,492,930.00  | 32.7%          |
| 04256038                  | PRESTR CONC GIRDER (TX46)               | LF   | \$145.00       | 8,096.910    | \$1,174,051.95 | \$6,666,981.95  | 39.7%          |
| 03446172                  | SUPERPAVE MIXTURES SP-C PG64-22(LEV-UP) | TON  | \$105.00       | 8,403.000    | \$882,315.00   | \$7,549,296.95  | 45.0%          |
| 04226001                  | REINF CONC SLAB                         | SF   | \$14.75        | 55,200.000   | \$814,200.00   | \$8,363,496.95  | 49.8%          |
| 03446047                  | SUPERPAVE MIXTURES SP-C SAC-A PG70-22   | TON  | \$97.00        | 6,836.000    | \$663,092.00   | \$9,026,588.95  | 53.8%          |
| 01326006                  | EMBANKMENT (FINAL)(DENS CONT)(TY C)     | CY   | \$7.75         | 51,283.000   | \$397,443.25   | \$9,424,032.20  | 56.2%          |
| 05126005                  | PORT CTB (FUR & INST)(F-SHAPE)(TY 1)    | LF   | \$80.00        | 4,920.000    | \$393,600.00   | \$9,817,632.20  | 58.5%          |
| 04326001                  | RIPRAP (CONC)(4 IN)                     | CY   | \$400.00       | 796.000      | \$318,400.00   | \$10,136,032.20 | 60.4%          |
| 05086001                  | CONSTRUCTING DETOURS                    | SY   | \$70.00        | 4,470.000    | \$312,900.00   | \$10,448,932.20 | 62.3%          |
| 04506014                  | RAIL (TY T551)                          | LF   | \$62.00        | 4,932.000    | \$305,784.00   | \$10,754,716.20 | 64.1%          |
| 04016001                  | FLOWABLE BACKFILL                       | CY   | \$180.00       | 1,647.000    | \$296,460.00   | \$11,051,176.20 | 65.9%          |
| 04166004                  | DRILL SHAFT (36 IN)                     | LF   | \$140.00       | 2,067.000    | \$289,380.00   | \$11,340,556.20 | 67.6%          |
| 04326036                  | RIPRAP (STONE PROTECTION)(30 IN)        | CY   | \$140.00       | 1,596.000    | \$223,440.00   | \$11,563,996.20 | 68.9%          |
| 04626018                  | CONC BOX CULV (7 FT X 7 FT)             | LF   | \$600.00       | 360.000      | \$216,000.00   | \$11,779,996.20 | 70.2%          |
| 04326002                  | RIPRAP (CONC)(5 IN)                     | CY   | \$400.00       | 529.000      | \$211,600.00   | \$11,991,596.20 | 71.5%          |
| 01006002                  | PREPARING ROW                           | STA  | \$3,000.00     | 65.090       | \$195,270.00   | \$12,186,866.20 | 72.6%          |
| 04206029                  | CL C CONC (CAP)                         | CY   | \$830.00       | 189.200      | \$157,036.00   | \$12,343,902.20 | 73.6%          |
| 01106003                  | EXCAVATION (SPECIAL)                    | CY   | \$7.00         | 19,500.000   | \$136,500.00   | \$12,480,402.20 | 74.4%          |
| 05456001                  | CRASH CUSH ATTEN (INSTL)                | EA   | \$10,500.00    | 13.000       | \$136,500.00   | \$12,616,902.20 | 75.2%          |
| 02756001                  | CEMENT                                  | TON  | \$160.00       | 819.000      | \$131,040.00   | \$12,747,942.20 | 76.0%          |
| 01646054                  | BOND FBR MTRX SEED (PERM)(RURAL)(SAND)  | SY   | \$0.82         | 154,000.000  | \$126,280.00   | \$12,874,222.20 | 76.7%          |
| 06816001                  | TEMP TRAF SIGNALS                       | EA   | \$60,000.00    | 2.000        | \$120,000.00   | \$12,994,222.20 | 77.4%          |
| 05146040                  | PERM CTB (SSCB)(TY 3)(MOD)              | LF   | \$360.00       | 330.000      | \$118,800.00   | \$13,113,022.20 | 78.1%          |
| 01106001                  | EXCAVATION (ROADWAY)                    | CY   | \$5.50         | 20,121.000   | \$110,665.50   | \$13,223,687.70 | 78.8%          |
| 05066002                  | ROCK FILTER DAMS (INSTALL) (TY 2)       | LF   | \$33.00        | 3,330.000    | \$109,890.00   | \$13,333,577.70 | 79.5%          |

Descending order

# Sorting & Mapping Process: a multi-step process

- Map pay items in monthly estimate to work activities in schedule

b. Map the pay items to work activities in schedule


|       |                                 |
|-------|---------------------------------|
| A1520 | LEVELING PADS - WALLS A, B, & C |
| A1530 | CONST WALL C                    |
| A1540 | CONST WALL A                    |
| A1550 | CONST WALL B                    |
| A1560 | SET COPING - WALLS A, B, & C    |

| Table of Project Estimate |   |      |                |              |                |                 |                |
|---------------------------|---|------|----------------|--------------|----------------|-----------------|----------------|
| ITEM CODE                 | DESCRIPTION                             | UNIT | UNIT PRICE     | BID QUANTITY | TOTAL PRICE    | CUMULATIVE COST | CUMULATIVE (%) |
| 03446034                  | SUPERPAVE MIXTURES SP-C PG64-22         | TON  | \$97.00        | 23,670.000   | \$2,295,990.00 | \$2,295,990.00  | 13.7%          |
| 04236001                  | RETAINING WALL (MSE)                    | SF   | \$60.00        | 29,949.000   | \$1,796,940.00 | \$4,092,930.00  | 24.4%          |
| 05006001                  | MOBILIZATION                            | LS   | \$1,400,000.00 | 1.000        | \$1,400,000.00 | \$5,492,930.00  | 32.7%          |
| 04256038                  | PRESTR CONC GIRDER (TX46)               | LF   | \$145.00       | 8,096.910    | \$1,174,051.95 | \$6,666,981.95  | 39.7%          |
| 03446172                  | SUPERPAVE MIXTURES SP-C PG64-22(LEV-UP) | TON  | \$105.00       | 8,403.000    | \$882,315.00   | \$7,549,296.95  | 45.0%          |
| 04226001                  | REINF CONC SLAB                         | SF   | \$14.75        | 55,200.000   | \$814,200.00   | \$8,363,496.95  | 49.8%          |
| 03446047                  | SUPERPAVE MIXTURES SP-C SAC-A PG70-22   | TON  | \$97.00        | 6,836.000    | \$663,092.00   | \$9,026,588.95  | 53.8%          |
| 01326006                  | EMBANKMENT (FINAL)(DENS CONT)(TY C)     | CY   | \$7.75         | 51,283.000   | \$397,443.25   | \$9,424,032.20  | 56.2%          |
| 05126005                  | PORT CTB (FUR & INST)(F-SHAPE)(TY 1)    | LF   | \$80.00        | 4,920.000    | \$393,600.00   | \$9,817,632.20  | 58.5%          |
| 04326001                  | RIPRAP (CONC)(4 IN)                     | CY   | \$400.00       | 796.000      | \$318,400.00   | \$10,136,032.20 | 60.4%          |
| 05086001                  | CONSTRUCTING DETOURS                    | SY   | \$70.00        | 4,470.000    | \$312,900.00   | \$10,448,932.20 | 62.3%          |
| 04506014                  | RAIL (TY T551)                          | LF   | \$62.00        | 4,932.000    | \$305,784.00   | \$10,754,716.20 | 64.1%          |
| 04016001                  | FLOWABLE BACKFILL                       | CY   | \$180.00       | 1,647.000    | \$296,460.00   | \$11,051,176.20 | 65.9%          |
| 04166004                  | DRILL SHAFT (36 IN)                     | LF   | \$140.00       | 2,067.000    | \$289,380.00   | \$11,340,556.20 | 67.6%          |
| 04326036                  | RIPRAP (STONE PROTECTION)(30 IN)        | CY   | \$140.00       | 1,596.000    | \$223,440.00   | \$11,563,996.20 | 68.9%          |
| 04626018                  | CONC BOX CULV (7 FT X 7 FT)             | LF   | \$600.00       | 360.000      | \$216,000.00   | \$11,779,996.20 | 70.2%          |
| 04326002                  | RIPRAP (CONC)(5 IN)                     | CY   | \$400.00       | 529.000      | \$211,600.00   | \$11,991,596.20 | 71.5%          |
| 01006002                  | PREPARING ROW                           | STA  | \$3,000.00     | 65.090       | \$195,270.00   | \$12,186,866.20 | 72.6%          |
| 04206029                  | CL C CONC (CAP)                         | CY   | \$830.00       | 189.200      | \$157,036.00   | \$12,343,902.20 | 73.6%          |
| 01106003                  | EXCAVATION (SPECIAL)                    | CY   | \$7.00         | 19,500.000   | \$136,500.00   | \$12,480,402.20 | 74.4%          |
| 05456001                  | CRASH CUSH ATTEN (INSTL)                | EA   | \$10,500.00    | 13.000       | \$136,500.00   | \$12,616,902.20 | 75.2%          |
| 02756001                  | CEMENT                                  | TON  | \$160.00       | 819.000      | \$131,040.00   | \$12,747,942.20 | 76.0%          |
| 01646054                  | BOND FBR MTRX SEED (PERM)(RURAL)(SAND)  | SY   | \$0.82         | 154,000.000  | \$126,280.00   | \$12,874,222.20 | 76.7%          |
| 06816001                  | TEMP TRAF SIGNALS                       | EA   | \$60,000.00    | 2.000        | \$120,000.00   | \$12,994,222.20 | 77.4%          |
| 05146040                  | PERM CTB (SSCB)(TY 3)(MOD)              | LF   | \$360.00       | 330.000      | \$118,800.00   | \$13,113,022.20 | 78.1%          |
| 01106001                  | EXCAVATION (ROADWAY)                    | CY   | \$5.50         | 20,121.000   | \$110,665.50   | \$13,223,687.70 | 78.8%          |
| 05066002                  | ROCK FILTER DAMS (INSTALL) (TY 2)       | LF   | \$33.00        | 3,330.000    | \$109,890.00   | \$13,333,577.70 | 79.5%          |

|       |                                      |     |       |      |    |           |           |
|-------|--------------------------------------|-----|-------|------|----|-----------|-----------|
| A1210 | INSTALL TEMP SPEC SHORING @ 468 - US | SF  | 600   | 100  | 6  | 06-Mar-19 | 13-Mar-19 |
| A1220 | INSTALL DBL 7X7 BOX CULV @ 468 - US  | LF  | 60    | 10   | 6  | 14-Mar-19 | 21-Mar-19 |
| A1230 | CONST WINGWALL @ 468 - US            | EA  | 1     | .17  | 6  | 21-Mar-19 | 28-Mar-19 |
| A1235 | PLACE ROCK RIPRAP @ 468 - US         | CY  | 42    | 30   | 2  | 28-Mar-19 | 02-Apr-19 |
| A1240 | INSTALL TEMP SPEC SHORING @ 468 - DS | SF  | 600   | 100  | 6  | 02-Apr-19 | 08-Apr-19 |
| A1250 | INSTALL DBL 7X7 BOX CULV @ 468 - DS  | LF  | 60    | 10   | 6  | 09-Apr-19 | 15-Apr-19 |
| A1260 | CONST WINGWALL @ 468 - DS            | EA  | 1     | .17  | 6  | 15-Apr-19 | 22-Apr-19 |
| A1270 | PLACE ROCK RIPRAP @ 468 - DS         | CY  | 651   | 30   | 20 | 22-Apr-19 | 14-May-19 |
| A1280 | INSTALL PIPE CROSSINGS NB            | LF  | 512   | 25   | 20 | 04-Jan-19 | 25-Jan-19 |
| A1290 | DRIVEWAYS AND PIPE/SET'S             | SY  | 1594  | 80   | 20 | 22-Nov-18 | 14-Dec-18 |
| A1295 | EARTHWORK                            | CY  | 10885 | 1000 | 20 | 14-May-19 | 08-Jun-19 |
| A1300 | 8" CEMENT TREATED SUBGRADE           | SY  | 5597  | 1000 | 6  | 06-Jun-19 | 13-Jun-19 |
| A1310 | 10" SUPERPAVE BASE                   | TON | 2911  | 600  | 5  | 13-Jun-19 | 19-Jun-19 |
| A1320 | OCST                                 | GAL | 3234  | 3500 | 1  | 19-Jun-19 | 20-Jun-19 |
| A1330 | 2" SUPERPAVE SURFACE                 | TON | 841   | 200  | 4  | 20-Jun-19 | 26-Jun-19 |
| A1340 | PAVEMENT MARKINGS                    | LS  | 1     | .2   | 5  | 26-Jun-19 | 02-Jul-19 |

# Sorting & Mapping Process: a multi-step process (Summary)

- Sort & Map pay items in monthly estimate (or estimate and quantity sheet) to work activities in schedule:



# Mapping Items from the E&Q or Estimate to the Schedule

## ■ Mapping Items

Independent

2. Consider a pay item as an activity

Combined

2. Combine similar pay items into one activity

Else

2. Break down pay items into one or multiple activities

Schedule Activities

|       |                                      |     |
|-------|--------------------------------------|-----|
| A1210 | INSTALL TEMP SPEC SHORING @ 468 - US | SF  |
| A1220 | INSTALL DBL 7X7 BOX CULV @ 468 - US  | LF  |
| A1230 | CONST WINGWALL @ 468 - US            | EA  |
| A1235 | PLACE ROCK RIPRAP @ 468 - US         | CY  |
| A1240 | INSTALL TEMP SPEC SHORING @ 468 - DS | SF  |
| A1250 | INSTALL DBL 7X7 BOX CULV @ 468 - DS  | LF  |
| A1260 | CONST WINGWALL @ 468 - DS            | EA  |
| A1270 | PLACE ROCK RIPRAP @ 468 - DS         | CY  |
| A1280 | INSTALL PIPE CROSSINGS NB            | LF  |
| A1290 | DRIVEWAYS AND PIPE/SET'S             | SY  |
| A1295 | EARTHWORK                            | CY  |
| A1300 | 8" CEMENT TREATED SUBGRADE           | SY  |
| A1310 | 10" SUPERPAVE BASE                   | TON |
| A1320 | OCST                                 | GAL |
| A1330 | 2" SUPERPAVE SURFACE                 | TON |
| A1340 | PAVEMENT MARKINGS                    | LS  |

|       |                                 |    |
|-------|---------------------------------|----|
| A1520 | LEVELING PADS - WALLS A, B, & C | LF |
| A1530 | CONST WALL C                    | SF |
| A1540 | CONST WALL A                    | SF |
| A1550 | CONST WALL B                    | SF |
| A1560 | SET COPING - WALLS A, B, & C    | LF |
| A1570 | LEVELING PADS - WALLS D & E     | LF |
| A1580 | CONST WALL D                    | SF |
| A1590 | CONST WALL E                    | SF |
| A1600 | SET COPING - WALLS D & E        | LF |

Contract Items

| ITEM CODE | DESCRIPTION                             | UNIT |
|-----------|---|------|
| 03446034  | SUPERPAVE MIXTURES SP-C PG64-22         | TON  |
| 04236001  | RETAINING WALL (MSE)                    | SF   |
| 05006001  | MOBILIZATION                            | LS   |
| 04256038  | PRESTR CONC GIRDER (TX46)               | LF   |
| 03446172  | SUPERPAVE MIXTURES SP-C PG64-22(LEV-UP) | TON  |
| 04226001  | REINF CONC SLAB                         | SF   |
| 03446047  | SUPERPAVE MIXTURES SP-C SAC-A PG70-22   | TON  |
| 01326006  | EMBANKMENT (FINAL)(DENS CONT)(TY C)     | CY   |
| 05126005  | PORT CTB (FUR & INST)(F-SHAPE)(TY 1)    | LF   |
| 04326001  | RIPRAP (CONC)(4 IN)                     | CY   |
| 05086001  | CONSTRUCTING DETOURS                    | SY   |
| 04506014  | RAIL (TY T551)                          | LF   |
| 04016001  | FLOWABLE BACKFILL                       | CY   |
| 04166004  | DRILL SHAFT (36 IN)                     | LF   |
| 04326036  | RIPRAP (STONE PROTECTION)(30 IN)        | CY   |
| 04626018  | CONC BOX CULV (7 FT X 7 FT)             | LF   |
| 04326002  | RIPRAP (CONC)(5 IN)                     | CY   |
| 01006002  | PREPARING ROW                           | STA  |
| 04206029  | CL C CONC (CAP)                         | CY   |
| 01106003  | EXCAVATION (SPECIAL)                    | CY   |
| 05456001  | CRASH CUSH ATTEN (INSTL)                | EA   |
| 02756001  | CEMENT                                  | TON  |
| 01646054  | BOND FBR MTRX SEED (PERM)(RURAL)(SAND)  | SY   |
| 06816001  | TEMP TRAF SIGNALS                       | EA   |
| 05146040  | PERM CTB (SSCB)(TY 3)(MOD)              | LF   |
| 01106001  | EXCAVATION (ROADWAY)                    | CY   |
| 05066002  | ROCK FILTER DAMS (INSTALL) (TY 2)       | LF   |

# Mapping Process: A starting point.

- Combine similar pay items into one activity
  - Using Experiences and Judgements
  - Using the First Four Digits of Item Code

| ITEM CODE | DESCRIPTION                             |
|-----------|---|
| 01006002  | PREPARING ROW                           |
| 01046017  | REMOVING CONC (DRIVEWAYS)               |
| 01106001  | EXCAVATION (ROADWAY)                    |
| 01326005  | EMBANKMENT (FINAL)(ORD COMP)(TY C)      |
| 01346002  | BACKFILL (TY B)                         |
| 01646041  | DRILL SEEDING (TEMP) (WARM)             |
| 02476057  | FL BS (CMP IN PLC)(TYE GR1-2)(FNAL POS) |
| 02756001  | CEMENT                                  |
| 02756002  | CEMENT TREAT (EXIST MATL) (6")          |
| 03106009  | PRIME COAT (MC-30)                      |
| 03166249  | A GGR(TY-PE GR-4 SAC-B)                 |
| 03166400  | ASPH (AC-15P OR AC-10-2TR OR CRS-2P)    |
| 03416010  | D-GR HMA TY-B PG70-22                   |

Example of Pay Items in Estimates

|                  |  |            |
|------------------|--|------------|
| <b>200 ITEMS</b> | <b>SUBGRADE TREATMENTS AND BASE</b> .....                              | <b>119</b> |
| 265              | Fly Ash or Lime-Fly Ash Treatment (Road-Mixed) .....                   | 147        |
| 275              | Cement Treatment (Road-Mixed).....                                     | 153        |
| 276              | Cement Treatment (Plant-Mixed) .....                                   | 158        |
| <b>300 ITEMS</b> | <b>SURFACE COURSES AND PAVEMENTS</b> .....                             | <b>171</b> |
| Item 300         | Asphalts, Oils, and Emulsions .....                                    | 173        |
| 301              | Asphalt Antistripping Agents.....                                      | 184        |
| 302              | Aggregates for Surface Treatments .....                                | 186        |
| 305              | Salvaging, Hauling, and Stockpiling Reclaimable Asphalt Pavement ..... | 189        |
| 310              | Prime Coat .....   | 190        |
| 314              | Emulsified Asphalt Treatment.....                                      | 192        |
| 315              | Fog Seal .....   | 194        |
| 316              | Seal Coat .....  | 195        |
| 320              | Equipment for Asphalt Concrete Pavement.....                           | 200        |

Standard Specifications for Construction and Maintenance of Highways, Streets, and Bridges (TxDOT, 2014)

# Reference for Mapping

- Create a list or use your own knowledge to consider which items might map to certain activities.
  - Controlling Activities for Highway Rehabilitation Projects in Texas DOT

| No.  | Major Work Items                 |
|--|----------------------------------|
| 1  | Initial traffic control          |
| 2  | Detour                           |
| 3  | <b>ROW Preparations</b>          |
|  | A. Major Structure demolition    |
|  | B. Clear and grub                |
|  | C. Remove old structures (small) |
|  | D. Remove old pavement           |
|  | E. Remove old curb & gutter      |
|  | F. Remove old sidewalks          |
| G. Remove old drainage/ utility structures |                                  |
| 4  | <b>Excavation/ embankment</b>    |
|  | A. Earth excavation              |
|  | B. Rock excavation               |
|  | C. Embankment                    |
| 5  | <b>Bridge structures</b>         |
|  | A. Erect temporary bridge        |
|  | B. Bridge demolition             |
|  | C. Cofferdams                    |
|  | D. Piling                        |
|  | E. Footings                      |
|  | F. Columns, Caps and Bents       |
|  | G. Wingwalls                     |
|  | H. Beams (erection only)         |
|  | I. Bridge deck (total depth)     |
|  | J. Bridge curbs/ walks           |
|  | K. Bridge handrails              |
|  | L. Remove temporary bridge       |

|    |  |
|----|--|
| 6  | <b>Retaining walls</b>                       |
| 7  | <b>Base preparations</b>                     |
|    | A. Lime stabilizations                       |
|    | B. Flexible base material                    |
|    | C. Cement treated base material              |
| 8  | <b>New curb and gutter</b>                   |
| 9  | <b>Hot Mix asphalt base</b>                  |
| 10 | <b>Concrete paving</b>                       |
| 11 | <b>Hot mix asphalt surface</b>               |
| 12 | <b>Precast traffic barriers</b>              |
| 13 | <b>Permanent signing and traffic signals</b> |
|    | A. Small signs                               |
|    | B. Overhead signs                            |
|    | C. Major traffic signals                     |
| 14 | <b>Seeding and landscape</b>                 |
| 15 | <b>Pavement markings</b>                     |
| 16 | <b>Final clean up</b>                        |



| Bridge |                         |
|--------|-------------------------|
| A1020  | EB Drill Shaft          |
| A1040  | EB Columns              |
| A1030  | WB Drill Shaft          |
| A1050  | WB Columns              |
| A1070  | Saw Cut Demo: Phase 1   |
| A1080  | Demo: Phase 1           |
| A1090  | Abutment 1 & 2: Phase 1 |
| A1100  | Bent Caps: 2 - 10       |
| A1180  | Pan Girder              |
| A1200  | Approach Slab           |
| A1190  | T-411 Rai               |



## **3. PRODUCTION RATE AND DURATION CHECKING**

---

# Production Rate Checking

- Article 8.5.2 requires the contractor to provide production rates on schedule submissions.
- Sometimes this does not happen, but it should be pretty easy to calculate.

| user_text1                                       | Activity ID | Activity Name                                | Unit | Plan Qty  | Orig P/R | OD   | RD   | Start             | Finish            | Float |
|--|-------------|--|------|-----------|----------|------|------|-------------------|-------------------|-------|
| <b>PARKER SH 199 - 0171-03-067 - 128 Wk Days</b> |             |  |      | 401047.00 |          | 128d | 128d | Jul-09-2018 07 AM | Jan-08-2019 05 PM | 0d    |
| <b>GENERAL</b>                                   |             |  |      | 6.00      |          | 128d | 128d | Jul-09-2018 07 AM | Jan-08-2019 05 PM | 0d    |
| 01   | MS101       | TIME CHARGES COMMENCE (MILESTONE)            |      |           |          | 0d   | 0d   | Jul-09-2018 07 AM |                   | 0d    |
| 02   | 502-6011    | PROJECT TIME (LOE)                           | MO   | 6.00      |          | 128d | 128d | Jul-09-2018 07 AM | Jan-08-2019 05 PM | 0d    |
| <b>CONSTRUCTION</b>                              |             |  |      | 401041.00 |          | 128d | 128d | Jul-09-2018 07 AM | Jan-08-2019 05 PM | 0d    |
| 01   | MS102       | CONSTRUCTION COMMENCEMENT (MILESTONE)        |      |           |          | 0d   | 0d   | Jul-09-2018 07 AM |                   | 0d    |
| 05   | 500-6001    | MOBILIZATION                                 | LS   | 1.00      |          | 2d   | 2d   | Jul-09-2018 07 AM | Jul-10-2018 05 PM | 0d    |
| 06   | 502-6001    | BARRICADES, SIGNS AND TRAFFIC HANDLING (LOE) | MO   | 6.00      |          | 128d | 128d | Jul-09-2018 07 AM | Jan-08-2019 05 PM | 0d    |
| 07   | 6001-6001   | PORTABLE CHANGEABLE MESSAGE SIGN (LOE)       | DAY  | 250.00    |          | 128d | 128d | Jul-09-2018 07 AM | Jan-08-2019 05 PM | 0d    |
| 08   | 506-641     | BIODEG EROSN CONT LOGS (INSTL)(12")          | LF   | 200.00    | 200      | 1d   | 1d   | Jul-11-2018 07 AM | Jul-11-2018 05 PM | 0d    |
| 09   | 354-6002-1  | PLAN & TEXT ASPH CONC PAV(0" TO 2") 1        | SY   | 116791.00 | 5839.55  | 20d  | 20d  | Jul-11-2018 07 AM | Aug-07-2018 05 PM | 0d    |
| 09.5   | 354-6002-2  | PLAN & TEXT ASPH CONC PAV(0" TO 2") 2        | SY   | 116791.00 | 5839.55  | 20d  | 20d  | Aug-08-2018 07 AM | Sep-05-2018 05 PM | 0d    |
| 10   | 662-ALL-1   | WORK ZONE STRIPING -ALL                      | LS   | 1.00      | 0.04     | 40d  | 40d  | Jul-11-2018 07 AM | Sep-05-2018 05 PM | 0d    |
| 11   | 351-6006    | FLEXIBLE PAVEMENT STRUCTURE REPAIR(10")      | SY   | 5500.00   | 687.50   | 8d   | 8d   | Sep-06-2018 07 AM | Sep-17-2018 05 PM | 0d    |
| 12   | 341-6278    | D-GR HMA TY-D PG 70-28(LEV-UP)(LTX ADD)      | TON  | 1000.00   | 1000     | 4d   | 4d   | Sep-18-2018 07 AM | Sep-21-2018 05 PM | 0d    |
| 13   | 662-ALL-2   | WORK ZONE STRIPING - ALL                     | LS   | 1.00      | 1        | 1d   | 1d   | Sep-21-2018 07 AM | Sep-21-2018 05 PM | 0d    |
| 14   | 341-6276-1  | D-GR HMA TY-D SAC-B PG70-28 (LATEX ADD) 1    | TON  | 16350.00  | 817.50   | 20d  | 20d  | Sep-24-2018 07 AM | Oct-19-2018 05 PM | 0d    |
| 14   | 341-6276-2  | D-GR HMA TY-D SAC-B PG70-28 (LATEX ADD) 2    | TON  | 13080.00  | 817.50   | 16d  | 16d  | Oct-22-2018 07 AM | Nov-12-2018 05 PM | 0d    |

- It is sometimes challenging to determine a production rate when the contractor combines several pay items into a single work activity.

# Production Rate Checking

- Compare the production rates and the proposed production rates of TxDOT
  - In accordance with the 2016-2017 Sunset Advisory Commission Staff Report Recommendation 3.7, TxDOT has updated construction production rate information based on analysis of survey data from the Texas districts. This value is updated every two years in March.



2022 Construction Production Rates

| LINE NO.         | MAJOR WORK ITEMS                   | UNITS | Production Rates |       |       |
|------------------|------------------------------------|-------|------------------|-------|-------|
|                  |                                    |       | LOW              | MED   | HIGH  |
| <b>100 ITEMS</b> |                                    |       |                  |       |       |
| 1                | PREPARING ROW                      | AC    | 1                | 3     | 6     |
| 2                | REMOVING CONC PAV                  | SY    | 1,000            | 2,000 | 3,000 |
| 3                | REMOVING CONC                      | CY    | 25               | 100   | 250   |
| 4                | REMOVING STAB BASE AND ASPH        | SY    | 1,500            | 3,000 | 4,500 |
| 5                | REMOVING STAB BASE AND ASPH        | CY    | 500              | 900   | 1,250 |
| 6                | EXCAVATION (ROADWAY)(EARTH)        | CY    | 500              | 2,000 | 3,500 |
| 7                | EXCAVATION (ROADWAY)(ROCK)         | CY    | 250              | 1,000 | 1,500 |
| 8                | EMBANKMENT                         | CY    | 500              | 2,000 | 4,000 |
| 10               | SEEDING/SOD                        | SY    | 800              | 2,000 | 3,500 |
| <b>200 ITEMS</b> |                                    |       |                  |       |       |
| 11               | FLEX BASE                          | CY    | 350              | 750   | 1,250 |
| 12               | REWORK BS MTL                      | CY    | 250              | 500   | 750   |
| 13               | LIME TRT                           | SY    | 500              | 2,500 | 4,000 |
| 14               | CEMENT TREAT                       | SY    | 1,500            | 2,500 | 3,000 |
| 15               | ASPHALT STAB BASE (PLANT PRODUCED) | TON   | 300              | 750   | 1,250 |
| <b>300 ITEMS</b> |                                    |       |                  |       |       |

# Production Rate Checking

- If production rate is not included, the value is calculated by the formula below.

$$\text{Production Rate} = \frac{\text{Total estimated quantity of the activity}}{\text{Activity Duration}}$$

1) Quantity from mapping process

| AGGREGATED ITEMS | UNIT | UNIT PRICE | BID QUANTITY | TOTAL PRICE |
|------------------|------|------------|--------------|-------------|
| DRILL SHAFT      | LF   | \$ 340     | 1180.000     | \$ 158,620  |

2) Duration

| Activity ID   | Activity Name  | BL1 Duration | Original Duration | Actual Duration | Start     | Finish    |
|---------------|----------------|--------------|-------------------|-----------------|-----------|-----------|
| <b>Bridge</b> |                | 116          | 116               | 0               | 30-Nov-12 | 15-May-13 |
| A1020         | EB Drill Shaft | 11           | 11                | 0               | 30-Nov-12 | 14-Dec-12 |
| A1040         | EB Columns     | 11           | 11                | 0               | 04-Dec-12 | 18-Dec-12 |
| A1030         | WB Drill Shaft | 16           | 16                | 0               | 17-Dec-12 | 10-Jan-13 |

3) Production Rate

- The production rate of Drill Shaft =  $1180 / (11 + 16) = 43.7$

|           |                                 | Revision Date: 31-Mar-20 | Page 1 of 2               |     |      |
|-----------|---------------------------------|--------------------------|---------------------------|-----|------|
| LINE NO.  | MAJOR WORK ITEMS                | UNITS                    | Proposed Production Rates |     |      |
|           |                                 |                          | LOW                       | MED | HIGH |
| 400 ITEMS |                                 |                          |                           |     |      |
| 27        | Temp Special Shoring/Cofferdams | SF                       | 100                       | 500 | 900  |
| 28        | Soil Nails/Rock Nails           | LF                       | 200                       | 400 | 700  |
| 29        | Drilled Shafts                  | LF                       | 30                        | 100 | 200  |

Construction Production Rates (TxDOT, 2020)

# Activity Duration Checking

- Check whether durations of work activities are appropriate for the length and complexity of work.
- Remember “**1/20 Rule**”:
  - If work package takes less than a **working day** ~ too small
  - If work package takes longer than **1 month of real working days** ~ too large
    - **Article 8.5.2** in the Standard Specifications **maximizes** and activity duration at **20 working days**





## **4. ACTIVITY RELATIONSHIP ASSESSMENT**

# Four Types of Logical relationships

## – Finish to Start (FS)

- Activity A must Finish before activity B can Start



Finish to Start



## – Start to Start (SS)

- Activity A must Start before activity B can Start



Start to Start



## – Finish to Finish (FF)

- Activity A must Finish before activity B can Finish


Finish to Finish



## – Start to Finish (SF)

- Activity A must Start before activity B Finishes





Start to Finish



Rare for highway projects

# Lag Time

- A lag time is the amount of time whereby a successor activity is required to be delayed with respect to a predecessor activity (PMBOK Guide, 6th Ed., 2017).






## 5. CRITICAL PATH IDENTIFICATION AND CHECKING

# Critical Path Method (CPM) Scheduling

- Basic Information
  - Critical path is the longest chain of dependent activities by which the duration of the chain accounts for the total project duration
  - An activity in the critical path is called a critical activity
  - Any delay in each critical activity would lead to a delay in the end date of the project
- Components of Critical Path
  - A list of all activities (i.e., WBS) required to complete the project
  - The duration that each activity will take to complete
  - The logical relationships between the activities
  - Logical end points such as milestones or deliverable items

# Critical Path Identification and Checking (1/2)

- In a preconstruction schedule, critical activities that are included in the critical path are identified and their reasonableness is assessed.






## List of critical activities

- Advanced Warning Signs
- SWPPP
- EB Drill Shaft
- EB Columns
- WB Columns
- Saw Cut Demo: Phase 1
- Demo: Phase 1
- Abutment 1 & 2: Phase 1
- Bent Caps: 2 – 10
- Pan Girder
- T-411 Rail
- Permanent EB Sign & Pav Marks
- Switch Traffic to New EB

# Critical Path Identification and Checking (2/2)

- In progress schedules, changes in critical activities and the critical path are identified and their reasonableness is assessed.






## **6. SCHEDULE-MONTHLY ESTIMATE AGREEMENT**

# What you need for monthly updates:

| 1000            | Project Duration         | 11-Jul-18 A | 15-Aug-19 | 26 |
|-----------------|--------------------------|-------------|-----------|----|
| <b>Phase II</b> |                          |             |           |    |
| 1140            | Cement Treat Subgrade    | 13-May-19 A | 09-Jul-19 | 5  |
| 1150            | 12" Flex Base            | 20-May-19 A | 19-Jul-19 | 8  |
| 1160            | MC-30 Prime Coat         | 03-Jun-19 A | 22-Jul-19 | 1  |
| 1170            | One Course Seal          | 10-Jun-19 A | 25-Jul-19 | 1  |
| 1180            | 2" HMA Type D            | 17-Jun-19 A | 29-Jul-19 | 2  |
| 1190            | Backfill & Dress Slopes  | 30-Jul-19   | 01-Aug-19 | 2  |
| <b>Phase I</b>  |                          |             |           |    |
| 2130            | STAs. 274-284, 305-329   | 02-Apr-19 A | 09-Jul-19 | 5  |
| 2180            | 12" Flex Base            | 01-May-19 A | 09-Jul-19 | 5  |
| 2280            | One Course Seal          | 14-Jun-19 A | 11-Jul-19 | 1  |
| 2290            | 2" HMA Type D            | 17-Jun-19 A | 16-Jul-19 | 3  |
| 2300            | Backfill & Dress Slopes  | 18-Jul-19   | 19-Jul-19 | 2  |
| 2310            | Remove ASB               | 18-Jul-19   | 23-Jul-19 | 4  |
| 2320            | Remove Concrete Pavement | 25-Jul-19   | 01-Aug-19 | 5  |
| 2330            | Compost & Revegetation   | 02-Aug-19   | 19-Aug-19 | 10 |
| 2340            | Remove PCTB              | 29-Jul-19   | 02-Aug-19 | 4  |
| 2350            | 2" HMA Type D Surface    | 05-Aug-19   | 08-Aug-19 | 3  |
| 2370            | Pavement Markings & Rum  | 09-Aug-19   | 15-Aug-19 | 4  |
| 2380            | Permanent Signage        | 02-Aug-19   | 13-Aug-19 | 7  |
| 2390            | PROJECT COMPLETE         |             | 15-Aug-19 | 0  |

(No WBS)



Did the contractor do what they planned to do?

| LINE NBR  | ITEM CODE | SP NBR | DESCRIPTION                     | UNIT | UNIT PRICE | QTY THIS ESTIMATE | AMOUNT PAID THIS ESTIMATE |           |        |             |      |            |                   |                           |      |          |     |                     |    |         |       |            |
|---|-----------|--------|---------------------------------|------|------------|-------------------|---------------------------|-----------|--------|-------------|------|------------|-------------------|---------------------------|------|----------|-----|---------------------|----|---------|-------|------------|
| 0105  | 01616017  | 000    | COMPOST MANUF TOPSOIL (4")      | SY   | 1.300      | 16,451.110        | \$21,386.44               |           |        |             |      |            |                   |                           |      |          |     |                     |    |         |       |            |
| 0115  | 01646042  | 000    | DRILL SEEDING (TEMP) (WARM)     | AC   | 403.000    | 3.400             | \$1,370.20                |           |        |             |      |            |                   |                           |      |          |     |                     |    |         |       |            |
| 0123  | 01646046  | 000    | STRAW OR HAY MULCHING           | AC   | 980.500    | 3.400             | \$3,333.70                |           |        |             |      |            |                   |                           |      |          |     |                     |    |         |       |            |
| 0165  | 03416040  | 000    | D-GR HMA TY-D PG64-22           | TON  | 95.000     | 493.980           | \$46,928.10               |           |        |             |      |            |                   |                           |      |          |     |                     |    |         |       |            |
| 0170  | 03416042  | 000    | D-GR HMA TY-D SAC-B PG70-22     | TON  | 108.000    | 1,460.890         | \$157,776.12              |           |        |             |      |            |                   |                           |      |          |     |                     |    |         |       |            |
| 0275  | 05086001  | 000    | CONSTRUCTING DETOURS            | SY   | 42.400     | 414.220           | \$17,562.93               |           |        |             |      |            |                   |                           |      |          |     |                     |    |         |       |            |
| 0285  | 05126029  | 000    | PORT CTB (MOVE)(F-SHAPE)(TY 1)  | LF   | 5.000      | 3,120.000         | \$15,600.00               |           |        |             |      |            |                   |                           |      |          |     |                     |    |         |       |            |
| 0315  | 05456003  | 000    | CRASH CUSH ATTEN (MOVE & RESET) | EA   | 1,300.000  | 3.000             | \$3,900.00                |           |        |             |      |            |                   |                           |      |          |     |                     |    |         |       |            |
| <table border="1"> <thead> <tr> <th>LINE NBR</th> <th>ITEM CODE</th> <th>SP NBR</th> <th>DESCRIPTION</th> <th>UNIT</th> <th>UNIT PRICE</th> <th>QTY THIS ESTIMATE</th> <th>AMOUNT PAID THIS ESTIMATE</th> </tr> </thead> <tbody> <tr> <td>0495</td> <td>04326006</td> <td>000</td> <td>RIPRAP (CONC)(CL B)</td> <td>CY</td> <td>500.000</td> <td>7.000</td> <td>\$3,500.00</td> </tr> </tbody> </table> |           |        |                                 |      |            |                   | LINE NBR                  | ITEM CODE | SP NBR | DESCRIPTION | UNIT | UNIT PRICE | QTY THIS ESTIMATE | AMOUNT PAID THIS ESTIMATE | 0495 | 04326006 | 000 | RIPRAP (CONC)(CL B) | CY | 500.000 | 7.000 | \$3,500.00 |
| LINE NBR  | ITEM CODE | SP NBR | DESCRIPTION                     | UNIT | UNIT PRICE | QTY THIS ESTIMATE | AMOUNT PAID THIS ESTIMATE |           |        |             |      |            |                   |                           |      |          |     |                     |    |         |       |            |
| 0495  | 04326006  | 000    | RIPRAP (CONC)(CL B)             | CY   | 500.000    | 7.000             | \$3,500.00                |           |        |             |      |            |                   |                           |      |          |     |                     |    |         |       |            |
| TOTAL ITEM EARNINGS THIS ESTIMATE   |           |        |                                 |      |            |                   | <b>\$271,357.49</b>       |           |        |             |      |            |                   |                           |      |          |     |                     |    |         |       |            |

Last Month's Schedule Update


Monthly Estimate

| 1000            | Project Duration         | 11-Jul-18 A | 23-Sep-19   | 30 |
|-----------------|--------------------------|-------------|-------------|----|
| <b>Phase II</b> |                          |             |             |    |
| 1140            | Cement Treat Subgrade    | 13-May-19 A | 12-Aug-19   | 7  |
| 1150            | 12" Flex Base            | 20-May-19 A | 27-Aug-19   | 11 |
| 1160            | MC-30 Prime Coat         | 03-Jun-19 A | 29-Aug-19   | 1  |
| 1170            | One Course Seal          | 10-Jun-19 A | 03-Sep-19   | 1  |
| 1180            | 2" HMA Type D            | 17-Jun-19 A | 10-Sep-19   | 2  |
| 1190            | Backfill & Dress Slopes  | 12-Sep-19   | 13-Sep-19   | 2  |
| <b>Phase I</b>  |                          |             |             |    |
| 2130            | STAs. 274-284, 305-329   | 02-Apr-19 A | 17-Jul-19 A | 0  |
| 2180            | 12" Flex Base            | 01-May-19 A | 17-Jul-19 A | 0  |
| 2280            | One Course Seal          | 14-Jun-19 A | 25-Jul-19 A | 0  |
| 2290            | 2" HMA Type D            | 17-Jun-19 A | 31-Jul-19 A | 0  |
| 2300            | Backfill & Dress Slopes  | 01-Aug-19   | 02-Aug-19   | 2  |
| 2310            | Remove ASB               | 01-Aug-19   | 06-Aug-19   | 4  |
| 2320            | Remove Concrete Pavement | 08-Aug-19   | 15-Aug-19   | 5  |
| 2330            | Compost & Revegetation   | 13-Aug-19   | 29-Aug-19   | 10 |
| 2340            | Remove PCTB              | 05-Sep-19   | 10-Sep-19   | 4  |
| 2350            | 2" HMA Type D Surface    | 12-Sep-19   | 16-Sep-19   | 3  |
| 2370            | Pavement Markings & Rum  | 17-Sep-19   | 23-Sep-19   | 4  |
| 2380            | Permanent Signage        | 13-Aug-19   | 29-Aug-19   | 10 |
| 2390            | PROJECT COMPLETE         |             | 23-Sep-19   | 0  |

Current Schedule Update

Did TxDOT pay the contractor for work completed?

Is the planned work reasonable?



# Key Checkpoints

- 1. Check whether a missing activity in the schedule or a missing item in the estimate exists.
- 2. Check whether the work progress is consistent with the payment amount.
- 3. Check the planned activities for next month are reasonable.
- 4. Compare the production rate in the progress schedule to that in the preconstruction schedule when major changes occur.

| Data Date: Jul-25-2018                         |  |      |           |                |          |       |        |       |               |               | PARKER |  |
|--|--|------|-----------|----------------|----------|-------|--------|-------|---------------|---------------|--------|--|
| Activity ID                                    | Activity Name                              | Unit | Plan Qty  | Cmpltd Phs Qty | Orig P/R | OD    | Actual | RD    | Start         | Finish        | Float  |  |
| <b>PARKER SH 199 - 017 1-03-067 - 128 Wk 1</b> |  |      | 435828.39 |                |          | 129d  | 14d    | 92d   | Jun-14-2018 A | Dec-04-2018   | 0d     |  |
| <b>GENERAL</b>                                 |  |      | 6.00      |                |          | 129d  | 14d    | 92d   | Jun-14-2018 A | Dec-04-2018   | 0d     |  |
| MS101  | CONSTRUCTION COMMENCEMENT (MILESTONE)      |      |           |                |          | 0d    | 0d     | 0d    | Jun-14-2018 A |               |        |  |
| 502-6011                                       | PROJECT TIME (LOE)                         | MO   | 6.00      |                |          | 128d  | 14d    | 92d   | Jun-14-2018 A | Dec-04-2018   | 0d     |  |
| TS101  | TIME SUSPENSION 1 (TXDOT APPROVED)         |      |           |                |          | 0d    | 0d     | 0d    | Jun-14-2018 A | Jul-09-2018 A |        |  |
| <b>CONSTRUCTION</b>                            |  |      | 435822.39 |                |          | 129d  | 14d    | 92d   | Jul-09-2018 A | Dec-04-2018   | 0d     |  |
| MS102  | CONSTRUCTION COMMENCEMENT (MILESTONE)      |      |           |                |          | 0d    | 0d     | 0d    | Jul-09-2018 A |               |        |  |
| 500-6001 (A)                                   | MOBILIZATION                               | LS   | 1.00      | 1              |          | 2d    | 1d 5h  | 0d    | Jul-09-2018 A | Jul-10-2018 A |        |  |
| 500-6001 (B)                                   | MOBILIZATION                               | LS   | 0.25      |                |          | 0d 5h | 0d     | 0d 5h | Jul-26-2018   | Jul-26-2018   | 91d 5h |  |
| 502-6001                                       | BARRICADES, SIGNS AND TRAFFIC HANDLING (LO | MO   | 6.00      |                |          | 128d  | 14d    | 92d   | Jul-09-2018 A | Dec-04-2018   | 0d     |  |
| 6001-6001                                      | PORTABLE CHANGEABLE MESSAGE SIGN (LOE)     | DAY  | 250.00    |                |          | 128d  | 14d    | 92d   | Jul-09-2018 A | Dec-04-2018   | 0d     |  |
| 506-641  | BIODEG EROSN CONT LOGS (INSTL) (12")       | LF   | 200.00    |                | 200      | 1d    | 0d     | 1d    | Jul-26-2018   | Jul-26-2018   | 91d    |  |
| 354-6002-1                                     | PLAN & TEXT ASPH CONC PAV(0" TO 2") 1      | SY   | 116791.00 | 116791         | 5839.55  | 20d   | 5d     | 0d    | Jul-09-2018 A | Jul-13-2018 A |        |  |
| 354-6002-2 (A)                                 | PLAN & TEXT ASPH CONC PAV(0" TO 2") 2      | SY   | 116791.00 | 82009.94       | 5839.55  | 20d   | 3d     | 0d    | Jul-16-2018 A | Jul-18-2018 A |        |  |
| 354-6002-2 (B)                                 | PLAN & TEXT ASPH CONC PAV(0" TO 2") 2      | SY   | 34781.00  |                | 5839.55  | 6d    | 0d     | 6d    | Jul-26-2018   | Aug-02-2018   | 0d     |  |
| 662-ALL-1 (A)                                  | WORK ZONE STRIPING -ALL                    | LS   | 1.00      | .86            | 0.04     | 40d   | 9d     | 0d    | Jul-09-2018 A | Jul-18-2018 A |        |  |
| 662-ALL-1 (B)                                  | WORK ZONE STRIPING -ALL                    | LS   | 0.14      |                | 0.04     | 5d 6h | 0d     | 5d 6h | Jul-26-2018   | Aug-02-2018   | 0d     |  |

Schedule

| CONTRACT ID 017103067 ESTIMATE 0002 CONTRACTOR'S ESTIMATE PACKAGE |           |              |  |             |             |                   |                           | Page 3 of 6        |                  |
|---|-----------|--------------|--|-------------|-------------|-------------------|---------------------------|--------------------|------------------|
| WORK PERFORMED THIS PERIOD  |           |              |  |             |             |                   |                           |                    |                  |
| PROJECT   |           | NH 2018(745) |  | CONTROL     |             | 017103067         |                           |                    |                  |
| CATEGORY  |           | 001          |  | DESCRIPTION |             | ALL ITEMS         |                           |                    |                  |
| LINE NBR  | ITEM CODE | SP NBR       | DESCRIPTION                            | UNIT        | PRICE       | QTY THIS ESTIMATE | AMOUNT PAID THIS ESTIMATE | Total Bid Quantity | QTY Paid To Date |
| 0075  | 03546002  | 000          | PLAN & TEXT ASPH CONC PAV(0" TO 2")    | SY          | 1,190       | 198,800.940       | \$236,573.12              | 233,682.00         | 198,800.94       |
| 0085  | 05006001  | 000          | MOBILIZATION                           | LS          | 172,000.000 | 0.750             | \$126,000.00              | 1.00               | 0.90             |
| 0090  | 05026001  | 000          | BARRICADES, SIGNS AND TRAFFIC HANDLING | MO          | 3,750.000   | 1.000             | \$3,750.00                | 6.00               | 6.00             |
| 0150  | 06626001  | 000          | WK ZN PAV MRK NON-REMOV (WZ)(BRY)      | LF          | 0.150       | 880.000           | \$132.00                  | 1,520.00           | 880.00           |
| 0155  | 06626004  | 000          | WK ZN PAV MRK NON-REMOV (WZ)(SLD)      | LF          | 0.150       | 97,541.000        | \$14,631.15               | 98,546.00          | 97,541.00        |
| 0160  | 06626012  | 000          | WK ZN PAV MRK NON-REMOV (WZ)(SLD)      | LF          | 0.320       | 872.000           | \$279.04                  | 1,700.00           | 872.00           |
| 0175  | 06626032  | 000          | WK ZN PAV MRK NON-REMOV (Y)(BRY)       | LF          | 0.150       | 9,320.000         | \$1,396.00                | 7,650.00           | 15,150.00        |
| 0180  | 06626034  | 000          | WK ZN PAV MRK NON-REMOV (Y)(SLD)       | LF          | 0.150       | 73,992.000        | \$11,096.89               | 98,546.00          | 130,480.00       |
| 0185  | 06626109  | 000          | WK ZN PAV MRK SHT TERM (TABTY) W       | EA          | 0.800       | 239.000           | \$191.20                  | 5,460.00           | 600.00           |
| 0190  | 06626111  | 000          | WK ZN PAV MRK SHT TERM (TABTY) Y-2     | EA          | 0.800       | 92.000            | \$73.60                   | 80.00              | 2,559.00         |
| 0250  | 60016001  | 000          | PORTABLE CHANGEABLE MESSAGE SIGN       | DAY         | 95.000      | 46.000            | \$4,560.00                | 250.00             | 208.00           |
| TOTAL ITEM EARNINGS THIS ESTIMATE                                 |           |              |  |             |             |                   | <b>\$401,686.91</b>       |                    |                  |

Monthly Estimate




# **BASIC CONSTRUCTION SCHEDULE ANALYSIS**

---

Implementation

# Recommended Communication Protocol




# Proactive Letters

- Preconstruction/Baseline Schedule Guideline letter to the contractor
  - Sent prior to the preconstruction meeting with enough time for the contractor to implement during schedule creation
  - Remind the contractor what is required in the Specifications
  - Set the expectations for schedule submissions
  - Establish the expectations for your office for schedule review
  
- Progress Update Guideline letter to the contractor
  - Sent prior to the creation of the first estimate
  - Remind the contractor what is required in monthly updates
  - Set the expectations for schedule updates
  - Provide your office with a baseline for review items

- Proactive is great, but in reality you still manage projects.
  - Requires a THOROUGH preconstruction/baseline schedule analysis
  - Requires monthly analysis of contractor updates
  - Requires engaging with the contractor to address schedule concerns
  - Vital for using the schedule as a project management tool
  - Helpful in establishing good documentation for time impacts or other disputes
- Use General Questions as a starting point for analysis
  - General Questions for preconstruction/baseline schedule analysis
  - General Questions for monthly update analysis

# Engage the Contractor



**Thank you!**

**Please remember to use  
the Qualtrics links in your  
email to take the surveys  
for today's materials.**